



CITY OF SMYRNA

**ADDENDUM #1
FOR
RFQ 18-015**

Resurfacing Project 2018

March 20, 2018

OWNER: CITY OF SMYRNA
2800 KING STREET
SMYRNA, GA 30080

PROGRAM MANAGER: CROY ENGINEERING, LLC
200 N. COBB PARKWAY, SUITE 413
MARIETTA, GA 30062



TABLE OF CONTENTS
RESURFACING PROJECT 2018
RFQ 18-015
ADDENDUM #1

- I. Questions & Answers
- II. Revised Bid Form
- III. Revised Street List

QUESTIONS AND ANSWERS
RESURFAING PROJECT 2018
RFQ 18-015
ADDENDUM #1

1. What is the project completion date and or duration for this project, I cannot find any dates in RFQ?
 - a) See revised Bid Form.
2. What is the Anticipated Notice to Proceed date for this project?
 - a) Anticipated start date would be April 30th.
3. What is the application rate and or lift thickness for the 9.5mm Type II paving work?
 - a) The spread rate will be 165lbs/yd².
4. Will all roads receive the same asphalt application rate and or lift thickness?
 - a) Yes all roads have the same application rate.
5. What kind of milling do you expect to do on each road, Full Width Milling? Or Edge Milling (7' wide)?
 - a) The list of streets has been updated to reflect this.
6. It appears that you are only milling and paving back on each road, no patching, is this correct?
 - a) There is 140 tons of patching set up in the contract and where needed, will be determined by the inspector.
7. How long of a duration will you allow traffic to run on the milled surfaces before the final 9.5mm Type II is placed?
 - a) Traffic will be allowed to run on milled surfaces for no more than 7 days. Please be aware that manholes will be lowered prior to the award of the contract and they will be covered with GAB. It will be the contractors responsibility to maintain these areas if surfaces are milled and rain washes GAB away.
8. What are the traffic control work restrictions for this project? Or can we work whenever feel it is most productive?
 - a) If you are working inside of a subdivision then the lane closures will be allowed from 7am-6pm Monday through Friday and 9am to 6pm on Saturday. All other roads will only have lane closures allowed from 9am to 4pm.
9. If the existing asphalt is above the gutter line do you expect to mill down just the thickness of the new overlay or more? If you intend to mill more than the overlay thickness can please identify how deep you intend to mill on each road.
 - a) All milling will be required to be 1.5 inches below the gutter line and need to be overlaid to flush with the gutter.

10. Do you intend for the contractor to temporarily stripe the roads to maintain traffic then come back in 30 days to place the final pavement markings?
- a) Temporary stop bars and cross walks will be required before thermoplastic is installed.
11. How do you intend to pay for temporary pavement markings?
- a) The bid form is revised and traffic control line item will be added. The cost of temporary pavement markings will be included in Traffic Control Lump Sum.
12. Would it be possible for you to provide the length & width dimensions for each of the roads along with the work scope that you intend to perform on each road? (Attached is an example of the information that we get from other city's for work like this, it makes it much better for the contractor to provide the most competitive bids.)
- a) Many of the roads have variable widths. Bidders should field verify roadway dimensions and conditions.
13. In the RFQ on page 6 paragraph 10 you tell us to complete a Vendor Questionnaire & Reference Form that is provided in the RFQ, However there is no questionnaire in the RFQ Document, will you please provide this via an Addendum?
- a) The vendor questionnaire is not required.
14. What are the sizes for the Loop Detector – 3 Each?
- a) The Loop detectors will be removed from the bid form. This work will be performed by the City at a later date.
15. Do you expect all of the paving to take place during daytime work hours or do you expect some roads to be paved at night?
- a) All work will be done from 7am to 6pm Monday through Friday and 9am to 6pm on Saturdays.
15. I was looking thru the 12 page bid document and did not see any Completion Duration or Date?
- a) See revised bid form.



**BID SPECIFICATIONS
RFQ 18-015
RESURFACING PROJECTS**

1. BASE BID:

Pursuant to and in compliance with the Advertisement for Bids and the Specifications relating to:

PROJECT NAME: RESURFACING PROJECTS

BID NUMBER: RFQ 18-015

including Addenda (list addenda, if any) _____, the undersigned, having become thoroughly familiar with terms and conditions of the specifications and with local conditions affecting the performance, progress and cost of the work that is to be completed, hereby proposes and agrees to fully perform the work within the **SIXTY (60)** days timeframe stated and in accordance with the specifications including furnishing any or all services, labor, materials, and equipment authorized by the City and to do all the work required to complete said work in accordance with the specifications for the following unit prices:

Item Number	Item Description	Unit	Quantity	Unit Price	Bid Price
1	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE II, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	5790		
2	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	60600		
3	BITUM TACK COAT	GAL	4850		
4	THERMOPLASTIC STOP BAR, 24 IN, WHITE	EA	34		
5	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	14186		
6	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	300		
7	THERMOPLASTIC SOLID TRAF STRIPE, 8 IN, WHITE	EA	635		
8	RECYCLED ASPH CONC PATCHING, INCL BITUM MATL & H LIME	TN	140		
9	THERMOPLASTIC PVMT MARKING, ARROW, TP 2	EA	2		
10	TRAFFIC CONTROL	LS	1		
11	CONTINGENCY			\$50,000	\$50,000

Total Bid _____

Please see attached list of streets and locations to be included in the 2018 Paving Projects.



RFQ 18-015

	ROAD NAME	BEGINNING	ENDING
1	Glendale Place (Full width mill)	South Cobb Drive	Glendale Circle SE
2	Wisteria Lane (6' edge mill)	Brentwood Drive	South Cobb Drive
3	Westbrook Drive (6' edge mill)	Magnolia Drive	South Cobb Drive
4	Springwood Drive SE (Full width mill)	King Springs Road	Cul-de-sac
5	Lea Court SE (Full width mill)	North Cul-de-sac	South Cul-de-sac
6	Diane Court (Full width mill)	North Cul-de-sac	South Cul-de-sac
7	Vinings Approach Drive SE (6' edge mill)	Cooper Lake Road	Vinings Estates Drive
8	Plumcrest Road SE (Full width mill)	Rebecca Lane	North Cul-de-sac
9	Plumcrest Circle SE (Full width mill)	Rebecca Lane	Rebecca Lane
10	King Street SE (Full width mill)	Church Street SE	Village Green Circle SE
11	Chrysler Avenue SE (6' edge mill)	Wells Drive SE	Cul-de-sac
12	Dodge Street SE (6' edge mill)	Wells Drive SE	Elizabeth Avenue SE
13	Mell Court SE (6' edge mill)	Wells Drive SE	Elizabeth Avenue SE
14	Wells Circle SE (6' edge mill)	Wells Drive SE	Cul-de-sac
15	Elizabeth Avenue SE (6' edge mill)	Mell Court SE	Chrysler Avenue SE
16	Wells Drive SE (6' edge mill)	Pat Mell Road SE	Cul-de-sac
17	Birch Street (Full width mill)	Glendale Place	Powder Springs Street
18	Glendale Circle (Full width mill)	Burbank Circle	Burbank Circle
19	Powder Springs St. (6' edge mill)	Hamby Street	South Cobb Dr.



Please complete and submit the Acknowledgements below:

ADDENDUM #1

REVISED ACKNOWLEDGEMENTS

_____ We acknowledge receipt of Addendum 1 and its contents are fully incorporated into RFQ 18-015.

Company Name

Signature

Printed Name

Title

Date